Journal Homepage: www.ijarpr.com ISSN: 3049-0103 (Online)

International Journal of Advance Research Publication and Reviews

Vol 03, Issue 10, pp 824-836, October, 2026

Managing Automated Sanitation Installation Projects in Poultry Plants Through Validation Milestones and Food Safety Audits

Prabhala Fardy

Cornell University, New York, USA

DOI : https://doi.org/10.5281/zenodo.23913689

ABSTRACT

Poultry processing requires effective sanitation to control microbial contamination, protect public health, and maintain confidence in food supply chains. Automated sanitation technologies offer opportunities to improve cleaning consistency, reduce manual exposure, and strengthen operational control. However, their benefits depend on installation projects that integrate engineering delivery with food safety requirements. This article examines how validation milestones and food safety audits can guide the management of automated sanitation installations in poultry plants. It presents an integrated approach linking project scope, hygienic design, procurement, contractor coordination, commissioning, and operational handover. Validation milestones establish documented acceptance criteria for equipment installation, cleaning performance, operating parameters, and staff readiness. Food safety audits provide complementary assurance by examining procedural compliance, traceability, corrective actions, and alignment with hazard analysis and critical control point systems. Particular attention is given to managing production interruptions, inaccessible surfaces, chemical compatibility, verification sampling, and changes to established sanitation procedures. The approach positions sanitation installation as a coordinated engineering and public health undertaking, with success assessed through delivery performance, demonstrated cleaning effectiveness, audit findings, and sustained operational compliance following handover and routine use.

Keywords: Automated sanitation; poultry processing; engineering project management; sanitation validation; food safety audits; hygienic design.

1. INTRODUCTION

1.1 Poultry Processing, Sanitation and Public Health

Sanitation is fundamental to controlling contamination in poultry processing, where equipment and food-contact surfaces must be maintained to prevent insanitary conditions and product adulteration [1]. Cleaning removes residues that can compromise subsequent disinfection, making sanitation a coordinated process rather than a single chemical application [2]. Equipment complexity, joints and inaccessible surfaces can restrict cleaning, particularly where design does not adequately support inspection and maintenance [3].

Organic residues, persistent moisture and intensive production create demanding operating conditions. Hygienic facilities therefore require suitable drainage, cleanable materials and layouts that facilitate cleaning and contamination control [4]. Reliable sanitation supports consumer protection and product integrity, while failures can disrupt production and undermine confidence in food supply chains. Automation offers potential improvements in application consistency and cleaning control [5]. However, benefits cannot be assumed from equipment purchase alone: appropriate design, installation, operating procedures and evidence of effective performance remain necessary for responsible implementation and acceptance.

1.2 Automated Sanitation Installation as an Engineering Project

Automated sanitation installations may incorporate foam application, fixed spray systems, cleaning-in-place and programmable controls. Automated cleaning solutions illustrate how equipment, chemical delivery and monitoring can be combined [5]. Technology selection must nevertheless reflect equipment geometry, soil characteristics and the distinction between open surfaces and enclosed circuits. Hygienic design principles apply throughout construction and installation, not merely during routine cleaning [3].

Retrofitting existing plants creates interfaces with production lines, water supplies, electrical systems and drainage. Restricted shutdown windows require careful sequencing, temporary protection and agreement on when production can safely resume. Facility design guidance highlights the

importance of utilities and waste arrangements that support hygienic operation [4].

Consequently, engineering teams must coordinate with sanitation personnel, food safety specialists, contractors and suppliers. Responsibilities should encompass testing, training, documentation and corrective work. Project success extends beyond completion within budget and schedule to delivery of worthwhile outcomes [6]. For sanitation installations, those outcomes must include demonstrated cleaning capability, operational readiness and accountable acceptance decisions.

1.3 Article Aim, Scope and Contribution

This article presents a conceptual framework for managing automated sanitation installation projects through validation milestones and food safety audits. It links project delivery with hygienic performance and operational acceptance, without claiming results from an implemented project. Validation guidance establishes the importance of evidence that control measures can achieve their intended outcomes [7]. Auditing provides a complementary examination of management arrangements and evidence against defined criteria [8].

The intended audience includes plant managers, project engineers, sanitation leaders, auditors and food safety professionals. The proposed contribution is a structured approach connecting requirements, design reviews, installation checks, functional testing, performance assessment and accountable handover. Milestones will define evidence needed before progression, while audits will examine procedural implementation and unresolved risks. The following section establishes the technical and managerial principles required to define success and distinguish equipment completion from verified readiness for routine operation.

2. TECHNICAL AND MANAGEMENT FOUNDATIONS

2.1 Automated Sanitation Technologies and Hygienic Design

Automated sanitation technologies perform different functions and must be selected within operating boundaries. Foam systems distribute cleaning chemicals across exposed surfaces, while spray systems direct liquids towards specified areas; commercial solutions combine application equipment with chemical delivery and monitoring [5]. Cleaning-in-place circulates cleaning media through suitable enclosed equipment without routine dismantling, requiring hygienically designed circuits and defined operating conditions [10].

Cleaning removes soil and residues, whereas disinfection or sanitising reduces microorganisms to an appropriate level; these functions should not be treated as interchangeable [9]. Their effectiveness depends on suitable procedures, chemical selection and operating parameters.

Automation cannot reliably reach surfaces shielded by unsuitable geometry, eliminate inaccessible crevices or correct inadequate drainage. Equipment must therefore support access, inspection, residue removal and maintenance. Materials should tolerate intended chemicals and temperatures without compromising product safety [4].

Installation planning must examine water availability, chemical storage and dosing, electrical connections, ventilation and effluent capacity. These interfaces establish constraints on achievable flow, coverage, exposure and discharge. Accordingly, technology approval should follow assessment of the complete sanitation environment rather than isolated equipment specifications or supplier claims about performance.

2.2 Project Governance and Food Safety Responsibilities

Project governance will assign explicit responsibilities and decision rights, consistent with structured project management guidance [11]. The sponsor will approve objectives, resources and major changes. The project manager will coordinate scope, schedule, cost, risks and communication. Engineering personnel will assess integration, utilities and technical testing, while sanitation personnel will define cleaning needs and practical operating requirements.

The food safety lead will review hazards, acceptance criteria, verification arrangements and implications for existing controls. Multidisciplinary expertise is important when developing and maintaining hazard-control systems [12]. Suppliers will provide specifications, installation support, operating limits, training and agreed test evidence. Contracts will identify responsibilities for deviations, corrective work and retesting.

Production targets may conflict with access restrictions, shutdown duration and time needed to investigate failures. The proposed framework will therefore require documented requirements, coordinated shutdown plans and controlled assessment of modifications. Escalation routes will identify who can stop testing, withhold acceptance or authorise progression. Food safety specialists will participate from design through handover, rather than review completed installations retrospectively. This approach recognises that worthwhile project outcomes extend beyond schedule compliance [6]. Approval decisions will record evidence, unresolved risks and the conditions attached to acceptance.

2.3 Validation, Verification and Audit: Distinct Functions

Validation establishes evidence that a control measure, when properly implemented, can achieve a specified food safety outcome under defined

conditions [7]. For sanitation installations, this requires a justified relationship between the cleaning approach, relevant residues or hazards, equipment configuration and intended operating conditions. It should not be reduced to confirming that machinery operates.

Verification examines whether established procedures are followed and controls continue to function as intended. Reviews of records, observations and appropriate measurements can contribute to this continuing assessment [13]. Audits systematically examine evidence against specified criteria, including organisational procedures and applicable requirements [8]. They assess conformity within their scope rather than guarantee the absence of contamination.

Commissioning checks establish installation and functional readiness, including connections, controls, alarms and operating sequences. Performance validation asks whether the sanitation approach achieves its intended result. A satisfactory audit, clean appearance or isolated negative sample cannot independently demonstrate complete effectiveness [12]. Conclusions require complementary evidence and consideration of sampling limitations. These distinctions provide the basis for measurable requirements, proportionate acceptance criteria and informed design and procurement decisions throughout the proposed sanitation installation project lifecycle.

3. PROJECT DEFINITION, DESIGN AND PROCUREMENT

3.1 Baseline Assessment and Problem Definition

Baseline assessment will review existing sanitation procedures, equipment layouts and contamination concerns before defining the installation scope. Historical inspection findings, verification results, corrective actions and audit records will identify recurring weaknesses. Such records contribute to understanding whether established controls are implemented and remain effective [13].

The team will measure cleaning duration, labour input, water consumption and chemical use across representative production conditions. Assessment will distinguish routine cleaning from exceptional events, including equipment failures, product changes and repeat cleaning. Access limitations, drainage constraints and shutdown availability will be documented alongside production volume.

The problem statement will identify the specific deficiency requiring investment, such as inconsistent coverage, excessive downtime or inaccessible cleaning points. Hygiene risk assessment supports connecting identified hazards with design and operational controls [14]. Baseline limitations, including incomplete records, uncertain measurements and seasonal variation, will be recorded so later comparisons do not mistake differences in operating conditions for installation benefits.

3.2 Scope, Requirements and Acceptance Criteria

Operational and food safety needs will be translated into a documented requirements specification before equipment selection. The specification will define surfaces and circuits covered, excluded areas, intended residues, production conditions and required cleaning functions. Hygienic integration guidance highlights the importance of interfaces between equipment, installation, automation and maintenance [19].

Requirements will identify operating ranges, utility demands, dosing arrangements, control sequences, alarms and operator interfaces. Expected records will include cycle completion, deviations and parameter histories where relevant. Maintainability provisions will address inspection access, replacement components and calibration. Relevant meat and poultry equipment hygiene standards can inform design requirements within their stated scope [20].

Acceptance criteria will specify measurable performance expectations, test conditions, responsible assessors and required evidence. Mandatory safety and hygiene provisions will be distinguished from desirable savings or convenience features. Multidisciplinary review will ensure that requirements reflect hazard-control needs [12].

A traceability matrix will connect each requirement to design decisions, supplier submissions, commissioning tests and final approval. Quality management principles support planned evidence and accountability throughout project delivery [17]. Unresolved requirements will remain visible rather than disappear during procurement negotiations.

3.3 Design Review and Hazard-Informed Planning

Design review will examine hygienic performance alongside electrical, mechanical and occupational safety. Machinery risk assessment provides a structured basis for identifying hazards and evaluating risk reduction throughout relevant lifecycle stages [15]. The review will involve engineering, sanitation, food safety, production and supplier representatives.

Construction activities may introduce dust, fragments, tools or contaminated water into processing areas. The proposed plan will therefore establish physical segregation, controlled access, protected equipment and cleaning requirements before production resumes. Overspray and altered drainage will be assessed for unintended movement of residues between hygiene zones. Chemical exposure, inaccessible surfaces and maintenance access will also receive consideration.

Failure analysis will examine incorrect dosing, inadequate pressure, blocked nozzles, incomplete coverage, control faults and unsuccessful recovery after interruption. Hygienic design risk management connects assessment with construction, integration and operational mitigation [14]. Where applicable, hazardous energy controls will be coordinated between plant personnel and contractors [16].

Each unresolved risk will have an owner, corrective action, completion date and closure evidence. Governance arrangements will define escalation and approval authority [18]. Design release will depend on documented decisions rather than assumed agreement.

3.4 Supplier Selection, Contracts and Delivery Planning

Supplier selection will assess technical capability, relevant sanitation experience, integration competence and commissioning support. Proposals will be compared against the approved requirements specification, including declared operating limits and exclusions. Hygienic integration considerations should extend beyond individual components to the assembled installation [19].

Procurement documents will specify drawings, manuals, training, spare parts, test protocols and responsibilities for performance evidence. Quality planning will define inspection points, acceptance records and treatment of nonconforming work [17]. Contractual milestones will link payment and progression to agreed evidence, rather than equipment delivery alone.

The installation schedule will coordinate access, shutdown allocation, utility isolation and activities involving other contractors. Where servicing involves hazardous energy, coordination will follow applicable procedures and responsibilities [16]. Contingency time will cover corrective work, cleaning, testing and controlled restart. Suppliers and plant representatives will agree responsibility for defects, retesting, warranty support and unresolved actions.

Changes affecting hygiene, functionality, cost or schedule will require documented impact assessment and approval through established governance [18]. Updated drawings and test requirements will follow authorised modifications. Once requirements and responsibilities are established, milestone gates will determine whether evidence exists to progress safely through installation, commissioning and operational acceptance.




Figure 1. Integrated project governance and food safety assurance architecture.

Plant requirements inform design, procurement, installation, commissioning and handover. Engineering, sanitation, food safety, production and supplier responsibilities operate across these stages, supported by documented change control, risk review and assurance. Milestone decisions link progression to agreed acceptance evidence.

4. VALIDATION MILESTONES AND INSTALLATION CONTROL

4.1 Milestone Architecture and Readiness Gates

The milestone sequence will comprise design approval, installation readiness, installation completion, operational testing and performance acceptance. Governance arrangements will identify authorised decision-makers and accountability for each gate [18]. Design approval will require agreed specifications and risk reviews; installation readiness will require access, resources, isolation arrangements and approved work instructions.

Installation completion will require inspection records and documented deviations. Operational testing will require evidence that functions perform within specified limits. Performance acceptance will require justified sanitation results under representative conditions. Hygienic integration requires attention to installation, automation, cleaning and maintenance interfaces [19].

Each unresolved action will have an owner, deadline and closure evidence. Conditional acceptance will be permitted only where outstanding items cannot compromise safety, required performance or evidence integrity. Failed criteria will trigger corrective work and proportionate retesting. Authorised personnel will stop unsafe work. Production restart will require documented release, not simply schedule completion or pressure to resume commercial operations.

4.2 Installation Qualification and Physical Completion

Installation qualification will compare the installed system with approved drawings, specifications and supplier requirements. Qualification terminology is adapted here as a project assurance structure, not presented as a universal poultry regulatory requirement; comparable installation and operational concepts are established in pharmaceutical guidance [21].

Engineering and sanitation representatives will inspect materials, pipework, joints, connections, spray devices and drainage. They will confirm utility availability, equipment identification and access for cleaning, inspection and maintenance. Applicable meat and poultry equipment hygiene criteria will inform assessment within their defined scope [20]. Installed interfaces will also be checked for unintended contamination pathways [19].

Instrument records will establish calibration status and suitability for intended measurements. Control panels, electrical protection, isolation provisions and relevant safety documentation will be reviewed by competent personnel. Missing labels, incomplete connections, damaged components and departures from drawings will enter a controlled deviation register.

Corrective actions will identify responsible parties and required closure evidence. Updated drawings and supporting records will form the completion dossier. Physical completion will establish readiness for functional testing; it will not independently authorise routine sanitation use or unrestricted production restart.

4.3 Operational Qualification and Functional Testing

Operational qualification will test whether the installed system performs its intended functions across approved operating ranges. This terminology draws on established qualification concepts, while acceptance conditions will remain specific to the poultry installation [21]. Tests will examine sequence execution, dosing, pressure, flow, cycle duration and temperature where these parameters influence the intended process.

Protocols will challenge alarms, interlocks, emergency stops and recovery after power or utility interruptions. Operators will demonstrate authorised cycle selection and responses to faults. Recording functions will be checked for completeness, timestamps and reliable identification of interrupted or unsuccessful cycles. Access controls will restrict changes to approved settings.

Testing will include relevant combinations of equipment use and utility demand rather than convenient conditions alone. Integration guidance recognises that automation and operational interfaces can affect hygienic performance [19]. Each test will record methods, expected outcomes, actual results, instruments and deviations. Failures will require correction and retesting before progression. Demonstrated functional control must precede performance validation because sanitation results are uninterpretable if operating conditions cannot be established and reproduced.

4.4 Performance Validation and Acceptance Decisions

Performance validation will evaluate the sanitation procedure under representative residues, equipment configurations and operating conditions. Commissioning guidance for chilled food environments recommends environmental sampling to assess intended cleaning and disinfection methods, with attention to problematic locations [22].

Visual inspection, residue assessment and microbiological testing will provide complementary evidence. Research in an avocado packing plant supports combining verification tools, although its findings cannot establish poultry-specific acceptance limits [23]. Sampling locations, repetitions, analytical methods and decision rules will be approved before testing. Difficult-to-clean surfaces and credible challenging conditions will receive attention. Microbial monitoring guidance distinguishes qualitative pathogen detection from quantitative assessment of organisms [24].

Failure will trigger investigation, corrective work and proportionate revalidation before acceptance. Qualified specialists will interpret results against predefined criteria, sampling limitations and intended use. Milestone testing establishes readiness at defined points; audits will subsequently examine whether management arrangements support reliable, sustained sanitation operation after the installation project closes.

Table 1. Validation milestones, acceptance evidence and approval responsibilities

Milestone	Requirement assessed	Evidence required	Acceptance basis	Responsible approver	Action following failure
Design approval	Suitability of proposed design and sanitation approach	Approved specifications, drawings, risk assessments and acceptance plan	Requirements addressed; significant risks resolved or controlled	Engineering lead and food safety lead	Revise design and repeat review
Installation readiness	Safe access, resources and work arrangements	Shutdown plan, isolation arrangements, segregation plan and approved instructions	Installation can proceed without uncontrolled risks to people, products or operations	Project manager with production and safety representatives	Withhold authorisation; resolve readiness gaps
Installation completion	Conformity of installed equipment with approved design	Inspection records, calibration evidence, updated drawings and deviation register	Installation requirements met; no outstanding defect prevents safe testing	Engineering lead with sanitation representative	Correct defects and repeat affected inspections
Operational testing	Reliable functionality within defined operating ranges	Approved test records covering sequences, dosing, utilities, alarms, interlocks and recovery	Specified functions and controls pass documented tests	Commissioning lead with engineering and sanitation approval	Investigate, correct and repeat affected tests
Performance acceptance	Effectiveness of the sanitation procedure under defined conditions	Visual findings, residue assessments, appropriate microbiological results and deviation closure	Predefined, justified acceptance criteria met across the approved protocol	Food safety lead with sanitation and engineering concurrence	Withhold acceptance; investigate and revalidate as necessary
Controlled operational release	Readiness for routine use and production restart	Signed acceptance, approved procedures, competency records, maintenance plan and outstanding-action review	Required evidence approved; responsibilities assigned; no unresolved safety-critical issue	Designated plant authority following required specialist approvals	Delay release or impose documented restrictions where justified

5. FOOD SAFETY AUDITS AND OPERATIONAL HANDOVER

5.1 Audit Planning and Evidence Selection

Audit planning will define the installation stages, equipment, procedures and organisational interfaces to be examined. Criteria will include approved specifications, contractual commitments, sanitation instructions and applicable requirements. Audits will be scheduled before handover and during early operation, with additional reviews triggered by significant deviations.

Auditors will be competent and sufficiently independent of the activities assessed to evaluate evidence objectively. Document review will examine installation records, approved procedures, training evidence, maintenance plans and corrective actions. Interviews will explore whether personnel understand responsibilities, while observation will compare actual practices with instructions. Record sampling will assess implementation over time rather than rely on selected successful cycles. Sanitation documentation requirements provide an important evidence base for implementation and monitoring [25].

High-risk equipment, difficult cleaning locations and interfaces with production will receive priority. Guidance on commissioning environmental sampling supports examining problematic areas [22]. Audits will assess whether technical testing is adequately planned, documented and acted upon;

they will not replace performance validation or specialist interpretation.

5.2 Sanitation Procedures and Hazard-Control Integration

Sanitation standard operating procedures will be revised to reflect the equipment, approved operating limits and assigned responsibilities. For federally inspected establishments, sanitation procedures must remain effective and current when facilities, equipment, operations or personnel change [25]. Instructions will specify equipment preparation, chemical preparation, authorised cycle selection, cleaning sequences, inspection and responses to unsuccessful cycles.

The food safety team will review how these changes interact with hazard analysis and existing controls. Altered chemical use, drainage or cleaning schedules may affect contamination pathways, residues and production release. No parameter will automatically become a critical control point merely because it is electronically monitored. Its classification will depend on the hazard analysis and control strategy.

Post-cleaning checks will combine appropriate observations and tests. Comparative research demonstrates that visual, ATP and microbial methods provide different information, supporting complementary assessment rather than interchangeability [23]. Revised procedures will receive identifiers, approval dates and controlled distribution. Configuration management supports identifying authorised versions and controlling changes [28]. Superseded instructions will be withdrawn, and staff will receive explanations before implementation.

5.3 Nonconformities, Corrective Actions and Change Control

Findings will be categorised according to their significance, the evidence available and the audit criteria applied. Immediate risks to product safety or worker protection will be escalated without waiting for routine reporting. Classification will guide response urgency but will not substitute for documented assessment.

Correction will address the immediate problem, such as repeating a failed cleaning cycle. Corrective action will investigate causes and prevent recurrence. Applicable sanitation requirements include restoring sanitary conditions and addressing potentially contaminated product, not merely completing administrative closure [26]. Each action will have an owner, completion date and effectiveness check.

Changes to chemicals, software, equipment configuration or cycle settings will undergo impact assessment before approval. Configuration management provides a basis for identifying changes and maintaining controlled records [28]. Additional functional testing or performance revalidation will be required when changes could affect previously accepted evidence or sanitation outcomes.

Closure will require evidence that actions were implemented and effective. Sampling approaches will match the question being investigated, recognising distinctions between qualitative and quantitative microbiological results [24]. Unresolved safety or readiness issues will remain escalated and prevent unrestricted acceptance.

5.4 Training, Competency and Handover Documentation

Training will prepare operators, sanitation personnel and maintenance staff for their specific responsibilities. Food hygiene guidance emphasises adapting instruction and evaluation to personnel needs and operational requirements [27]. Operators will practise cycle selection and fault response; sanitation staff will demonstrate preparation, inspection and escalation; maintenance personnel will address isolation, servicing and restoration.

Supervised practice and observed performance will establish competence rather than attendance alone. Competence management guidance supports assessing development needs and evaluating whether personnel can achieve intended outcomes [29].

The handover package will contain approved drawings, manuals, procedures, test reports, training records, calibration information and maintenance schedules. Outstanding actions will identify owners, deadlines and operating restrictions. Formal acceptance will transfer agreed operational responsibilities while preserving contractual supplier obligations. Support contacts, warranty conditions, spare-part arrangements and escalation routes will remain documented so the plant can resolve faults after project closure.

5.5 Post-Handover Verification and Continuing Assurance

Early operation will include intensified review of recurring faults, cleaning failures, deviations and audit findings. Monitoring will use defined responsibilities, review intervals and escalation thresholds. Applicable sanitation requirements call for continuing evaluation and revision when procedures cease to be effective [25].

Maintenance, recalibration and refresher training will respond to equipment condition, performance trends and identified competence gaps [29]. Reassessment will follow significant changes, repeated failures or evidence that accepted conditions are no longer maintained. Continuing assurance will therefore address sustained sanitation performance rather than installation completion. The following section evaluates engineering delivery and food safety outcomes together using interpretable indicators.




Figure 2. Validation milestone and audit feedback pathway.

6. PERFORMANCE EVALUATION, LIMITATIONS AND PRACTICAL IMPLICATIONS

6.1 Integrated Performance Indicators

Evaluation will combine delivery, sanitation performance and operational sustainability. Project indicators will include schedule adherence, cost variation, authorised change orders, shutdown duration and defects outstanding at handover. Each indicator will have a defined calculation, reporting period and accountable owner. Manufacturing indicator guidance emphasises explicit definitions, units and contextual interpretation [30].

Sanitation indicators will include accepted cleaning results, repeat-cleaning frequency, unsuccessful cycles, deviations and verification trends. Water, chemical, energy and labour use will be reported where reliable measurements exist, with appropriate denominators such as production throughput or completed cleaning cycles. Energy-related indicators require defined boundaries and consistent measurement [35].

Audit closure rates will distinguish completed actions from actions demonstrated to be effective. Competency records will identify assessed personnel and reassessment needs [29]. Equipment availability will account for planned maintenance and unexpected failures. Configuration histories will help interpret changes in settings or components [28].

These measures describe processes and performance; they do not directly quantify reduced foodborne illness. Claims about public health benefits would require additional evidence connecting sanitation improvements with relevant exposure and health outcomes, rather than assuming equivalence between them.

6.2 Evaluation Design and Interpretation

The proposed evaluation will compare baseline and post-installation periods, separating commissioning instability from routine operation. Observation windows will cover representative shifts, cleaning frequencies and production conditions. Where sufficient repeated observations exist, interrupted time-series analysis may examine changes in level and trend while considering seasonality and autocorrelation [31].

Production volume, product mix, staffing, equipment changes and concurrent hygiene initiatives will be recorded. Suitable comparison lines may strengthen interpretation when they share relevant operating conditions without receiving the installation. Controlled time-series guidance explains how comparisons can address some competing explanations, while retaining design-specific limitations [32].

Sampling locations, methods, timing and laboratories will remain consistent where feasible. Calibration, record completeness and coding rules will be checked before analysis. Missing observations and their reasons will be reported, with sensitivity analyses where justified.

Improvement will not automatically be attributed to automation if training, procedures or production conditions changed simultaneously. Complex intervention guidance emphasises interactions between intervention components and context [34]. Estimates will include uncertainty and operational explanations, distinguishing exploratory associations from credible evidence of causal effects within the evaluated poultry processing environment and observation period.

Table 2. Integrated project delivery and sanitation performance evaluation matrix

Evaluation domain	Indicator	Baseline measure	Post-installation measure	Data source	Interpretation limitation
Schedule performance	Milestone delays; shutdown duration	Approved project schedule and shutdown allowance	Actual milestone dates and shutdown hours	Schedule updates; shutdown logs	Approved scope changes may explain delays
Cost performance	Cost variation; change-order value	Approved budget and contingency	Final expenditure and authorised changes	Financial records; change register	Separate scope additions from overruns
Handover quality	Outstanding defects; corrective rework	Acceptance criteria and planned completion requirements	Defects at handover; closure time; rework hours	Inspection records; deviation register	Defect counts require severity classification
Cleaning effectiveness	Results meeting predefined criteria	Results from representative existing procedures	Comparable results under the installed procedure	Inspection, residue and microbiological records	Methods measure different aspects of cleanliness
Repeat cleaning	Repeat cycles per completed cleaning event	Existing repeat-cleaning rate	Post-installation rate using the same definition	Sanitation logs; cycle records	Detection practices and reporting may change
Resource consumption	Water, chemicals, energy and labour	Consumption within defined operating boundaries	Comparable consumption per cycle and production unit	Meters; dosing records; timesheets	Production mix and cleaning frequency affect comparisons
Equipment reliability	Availability; unplanned downtime	Existing system availability, where comparable	Installed system availability and failure history	Maintenance system; fault logs	Equipment age and operating demands may differ
Audit performance	Overdue actions; verified closure rate	Historical findings and closure performance	Findings, closure time and effectiveness checks	Audit reports; action register	Different audit scopes can distort trends
Workforce competence	Personnel meeting role-specific criteria	Pre-installation assessment, where available	Demonstrated competence and reassessment results	Observation checklists; training records	Attendance alone does not establish competence
Verification performance	Deviations; recurring adverse trends	Historical results from defined sampling points	Results using comparable methods and timing	Verification records; laboratory reports	Missing data and altered sampling limit inference

6.3 Practical Constraints and Implementation Limitations

Financial constraints may limit equipment specification, testing resources and the time available for corrective work. Restricted shutdown windows can encourage premature restart, while older layouts may constrain drainage, access and separation between activities. These limitations should be documented before interpreting installation performance.

Supplier dependence may affect software access, replacement components and fault diagnosis. Spare-part delays and limited maintenance capability can undermine availability despite satisfactory testing. Asset management guidance supports considering performance, risk and expenditure across the asset lifecycle [33].

Staff turnover may weaken operating knowledge, particularly when training records capture attendance rather than demonstrated competence [29]. Inconsistent procedures and incomplete records can obscure failures or exaggerate improvements. Configuration control will remain important when settings, components or software change [28].

Results from one plant may not transfer to facilities with different products, equipment geometry or operating cultures. An efficient programmed cycle may still leave poorly designed interfaces inadequately cleaned. Resource savings must therefore be considered alongside cleaning effectiveness, worker safety and long-term reliability. Lower consumption alone will not justify acceptance where essential sanitation outcomes remain uncertain or repeatedly fail assessment criteria.

6.4 Management Implications and Future Research

Project sponsors should fund assurance activities and protect time for testing, while engineers and food safety teams should jointly define acceptance evidence. Regulators will assess applicable compliance requirements; internal milestone approval will not replace their authority. Management decisions should consider lifecycle performance rather than acquisition costs alone [33].

Research should examine whether milestone-based management reduces rework, delayed acceptance and recurring failures. Comparative studies should distinguish the effects of automation from training, procedural changes and improved maintenance [34]. Multisite designs and longer follow-up will help assess transferability, equipment reliability and sustained sanitation performance.

Further priorities include lifecycle costs, audit effectiveness, competency retention and the consequences of supplier dependence. Resource evaluation should use consistent measurement boundaries, including energy consumption [35]. Findings should inform investment decisions, maintenance planning and future installation requirements. The framework offers a testable management approach, not demonstrated evidence of improvement. The conclusion therefore brings these principles together with the conditions needed for responsible, evidence-based sanitation automation in poultry plants.



Figure 3. Integrated sanitation project performance and continuous improvement framework.

7. CONCLUSION

7.1 Framework Summary and Practical Contribution

Installing sanitation automation within operating poultry plants requires coordination between engineering work, production constraints and food safety responsibilities. The proposed framework connects documented requirements, hygienic design, validation milestones, audits and controlled handover within a project lifecycle. Engineering teams establish technical readiness, sanitation personnel assess practical cleaning needs, production teams coordinate access, and food safety specialists interpret acceptance evidence. Their shared decisions must address unresolved risks before routine operation begins. Successful delivery therefore extends beyond equipment installation, schedule adherence and budget control. It requires demonstrated functionality, justified sanitation performance, competent personnel and approved operating arrangements. This approach provides a structured basis for accountable acceptance without presenting anticipated benefits as established results.

7.2 Conditions for Responsible Implementation

Responsible implementation depends on competent oversight, documented acceptance criteria and continuing verification after handover. Each plant must adapt the framework to its equipment, residues, operating conditions and applicable requirements. Testing and audit evidence should support decisions within clearly defined limits, with corrective action and reassessment when performance deteriorates. Resource savings and improved process indicators must not be equated with reduced public health risk without supporting data. Subject to appropriate evaluation, disciplined project management may support reliable sanitation, informed investment and sustained food safety performance throughout the installed system's operational lifecycle.

REFERENCE

1. Aliee M. *Integration Of Fluorescence Imaging And Advanced Analytical Techniques For Reliable Contamination Detection* (Doctoral dissertation, The University of North Dakota).
2. Bezpartochnyi M. Resilience, management, sustainability, and interdisciplinarity, pillars in business. HSSE Publishing Complex. 2024 Jan 1.
3. Alebiosu O. Comparative analysis of public-private partnership legislation driving electricity infrastructure expansion, renewable energy investment, and economic resilience nationally. Int J Foreign Trade Int Bus. 2025;7(2):239-249.
4. Blanc F. Inspection reforms: why, how, and with what results. Paris: Oecd; 2012.
5. Hiremath BN, Misra H. Management of livelihood centric rural development projects: A systemic view. InSecond National Conference on Agro-Informatics and Precision Farming, University of Agricultural Sciences, Raichur, organized by INSAIT, Dharwad 2009 Dec (pp. 2-3).
6. Chukwunweike J. Coordinating PLC-based load shedding and variable-speed drives to prevent transformer overloading during industrial production peaks. Int J Electr Data Commun. 2025;6(2 Pt B):118-135. doi:10.22271/27083969.2025.v6.i2b.109.
7. Litman N. Combat Ration Network for Technology Implementation. Multiple-Unit MRE Leak Detector. 2000 Jul 1.
8. Miller T, Durlik I, Kostecka E, Kozlovska P, Łobodzińska A, Sokołowska S, Nowy A. Integrating artificial intelligence agents with the internet of things for enhanced environmental monitoring: applications in water quality and climate data. Electronics. 2025 Feb 11;14(4):696.
9. Usen J. Food safety practices, policy interventions and the reduction of public health risks in the US. Magna Sci Adv Res Rev. 2021;3(2):152-166. doi:10.30574/msarr.2021.3.2.0095.
10. Drizo A. Phosphorus pollution control: policies and strategies. John Wiley & Sons; 2019 Dec 23.
11. Skerman A, Tait S. Bioenergy Support Program-DAF Transition Project 4C-116.
12. Ogan RK. Machine-learning-based API failure prediction and root-cause analytics for improving reliability of enterprise banking integration architectures at scale. Int J Comput Artif Intell. 2021;2(2):142-153. DOI:10.33545/27076571.2021.v2.i2a.378.
13. Shays C, editor. Food Safety: Oversight of the Centers for Disease Control Monitoring of Foodborne Pathogens: Congressional Hearing. DIANE Publishing; 1999.
14. Karlis P, Presicce F, Giner-Santonja G, Brinkmann T, Roudier S. Best Available Techniques (BAT) Reference Document for the slaughterhouses, animal by-products and/or edible co-products industries. Luxembourg: Publication Office of the European Union. doi. 2024 Feb 14;10:18199.

15. Alebiosu O. Engineering stakeholder alignment frameworks for resolving land rights, environmental compliance, and project delivery conflicts. Int J Appl Res. 2024;10(12):401-412.

16. Kumar A, Kumar D, Sharma RA. HACCP Applications and Challenges. Techsar Pvt. Ltd.; 2019 Jun 1.

17. Dollard RM. 2 Current Good. Good Design Practices for GMP Pharmaceutical Facilities. 2016 Aug 19:45.

18. Iyanuoluwa Oluwafemi. (2024). ENVIRONMENTAL MONITORING STRATEGIES INTEGRATING MOLECULAR DETECTION TECHNOLOGIES TO ENHANCE AGRICULTURAL BIOSECURITY AND SUSTAINABLE CROP PRODUCTION SYSTEMS. International Journal Of Engineering Technology Research & Management (IJETRM), 10(12), 757–772. https://doi.org/10.5281/zenodo.21152414

19. Mishra DK, Ozadali F, Benyathiar P, David JR. Establishing "validated state" of aseptic processing and packaging systems. InHandbook of aseptic processing and packaging 2022 Sep 9 (pp. 355-394). CRC Press.

20. Kunz Cechinel A, Soares CE, Pfleger SG, De Oliveira LL, Américo de Andrade E, Damo Bertoli C, De Rolt CR, De Pieri ER, Plentz PD, Röning J. Mobile robot+ IoT: Project of sustainable technology for sanitizing broiler poultry litter. Sensors. 2024 May 11;24(10):3049.

21. Alebiosu O. Quantifying regulatory delay risk transmission across utility-scale renewable energy projects in hydrocarbon-dominant economies. Int J Hydropower Civ Eng. 2023;4(1):35-47

22. Sun Q, Yuan Y, Xu B, Gao S, Zhai X, Xu F, Shi J. Innovative technologies reshaping meat industrialization: Challenges and opportunities in the intelligent era. Foods. 2025 Jun 24;14(13):2230.

23. Kolikipogu R, Shivaputra, Muniyandy E, Maroor JP, Lakshmi GV, Konduri B, Naveenkumar R. Improving food safety by IoT-based climate monitoring and control systems for food processing plants. Remote Sensing in Earth Systems Sciences. 2025 Jun;8(2):387-99.

24. Emmanuel Uzoh. (2023). PREDICTIVE OPERATIONS INTELLIGENCE: AN AUTOMATED MACHINELEARNING SYSTEM FOR BOTTLENECK DETECTION AND DYNAMIC WORKSTREAM PRIORITIZATION IN SMALL AND MEDIUM-SIZED ENTERPRISES. INTERNATIONAL JOURNAL OF ENGINEERING TECHNOLOGY RESEARCH & MANAGEMENT (IJETRM), 07(12), 793–806. https://doi.org/10.5281/zenodo.22089397

25. Arduser L, Brown DR. HACCP and sanitation in restaurants and food service operations. Atlantic Publishing Company; 2005.

26. George AS. Humanoid robots as poultry partners: Enhancing welfare through collaboration on the farm. Partners Universal International Research Journal. 2024 Mar 25;3(1):183-99.

27. Uchenna Emmanuel Boniface, Charles Sunday Mayaki. (2024). HIGH VOLTAGE ENGINEERING INNOVATIONS ENABLING EFFICIENT TRANSMISSION REDUCED LOSSES ENHANCED RELIABILITY SUSTAINABILITY ACROSS MODERN POWER NETWORKS WORLDWIDE INFRASTRUCTURE. International Journal Of Engineering Technology Research & Management (IJETRM), 08(03). https://doi.org/10.5281/zenodo.18116695

28. Kazimoto R. *The Contribution of the Poultry Farming Project to the Improvement of Food Security and Income Generating in Kunduchi Mtongani Community-Kinondoni Municipal* (Doctoral dissertation, The Open University of Tanzania).

29. Rosenthal I, Kunreuther H. Roles for third parties in implementing usda food safety and inspection service (FSIS)'s food safety process management programs. Risk Management and Decision Processes Center, The Wharton School of the University of Pennsylvania. 2010.

30. Bugeja Z. Evaluating The Level Of Food Safety Management Of Culinary Art Students At The Institute Of Tourism Studies. The Online Open Access Repository of the Institute of Tourism Studies (Malta). 2025 May 30.

31. Jagtap S, Rahimifard S. The digitisation of food manufacturing to reduce waste–Case study of a ready meal factory. Waste management. 2019 Mar 15;87:387-97.

32. Paiva CL. Quality management: Important aspects for the food industry. Food industry. 2013 Jan 16;9:191-2.

33. Oliver EL. Implementation of ISO/IEC 17025 practices in small and academic laboratories. The University of Nebraska-Lincoln; 2018.

34. Denkyi F. Defect engineering in gallium nitride semiconductors for improving carrier mobility and high-power electronic device reliability. International Journal of Research Publication and Reviews. 2026;7(9):3330-3342. doi:10.55248/gengpi.07.0926.3029.

35. Dyckman L. Effective food security strategies. Bioterror Food Saf. 2004 Dec 28;133.